

A detailed wireframe model of a particle accelerator, showing a large circular ring structure in the foreground and a more complex, multi-sectioned structure in the background.

# Experiences from medical LINAC commissioning

ARIES Workshop  
Experiences During Hadron Linac Commissioning

Bernhard Schlitt, GSI

January 26, 2021

- Dedicated ion beam therapy centers (synchrotrons)
- HIT & CNAO facility overviews
- Injector linac design & commissioning
- Conclusions

# Dedicated (Carbon) Ion Beam Therapy Centers (Based on Synchrotrons)



| Center   |         | Start | Injector                               |
|--|---------|-------|--|
| HIMAC - Heavy Ion Medical Accelerator in Chiba   | Japan   | 1994  | Alvarez                                |
| HIBMC - Hyogo Ion Beam Medical Center            | Japan   | 2002  | Alvarez                                |
| GHMC - Gunma University Heavy Ion Medical Center | Japan   | 2010  | 200 MHz<br>APF-<br>IH-DTL<br>4 MeV/u   |
| SAGA HIMAT, Tosu                                 | Japan   | 2013  |  |
| i-ROCK Kanagawa Cancer Center, Yokohama          | Japan   | 2015  |  |
| Osaka Heavy Ion Therapy Center                   | Japan   | 2018  |  |
| HIT - Heidelberg Ion Beam Therapy Center         | Germany | 2009  | 217 MHz<br>KONUS-<br>IH-DTL<br>7 MeV/u |
| CNAO, Pavia                                      | Italy   | 2011  |  |
| SPHIC - Shanghai Proton and Heavy Ion Center     | China   | 2014  |  |
| MIT - Marburg Ion Beam Therapy Center            | Germany | 2015  |  |
| MedAustron, Wiener Neustadt                      | Austria | 2016  |  |
| Heavy Ion Cancer Treatment Center, Wuwei         | China   | 2019  | (Cyclotron)                            |

**8 additional facilities worldwide  
under construction / planning**

# HIT

## Heidelberg Ion Beam Therapy Center




Ion Sources  
& Linac

Synchrotron

Developed by




Quality  
Assurance &  
Experiments



|   |   |
|---|---|
| Ion species                             | $^{12}\text{C}$ , $p$ , ( $^4\text{He}$ , $^{16}\text{O}$ ) |
| Max. beam energy                        | 220 – 430 MeV/u   |
| Pencil beam scanning at all four places |   |
| Footprint                               | 60 × 70 m <sup>2</sup>                                      |
| Capability                              | 1000 patients / year  |
| First patient                           | Nov. 2009   |






Linac installed  
inside synchrotron

Synchrotron:  
PIMMS design

Courtesy CNAO

# 217 MHz HIT Injector Linac

B. Schlitt, LINAC 2008



- ECR 1                       $\text{H}_3^+$  ( $\leq 1.3 \text{ mA}$ )
- ECR 2                       $\text{C}^{4+}$  ( $\leq 220 \mu\text{A}$ )
- ECR 3                      helium & oxygen beams + redundancy
- Pulsed beams               $\leq 300 \mu\text{s}$  @  $\leq 5 \text{ Hz}$
- Operating frequency      216.8 MHz

T. Winkelmann et al., ECRIS 2014

M. Schwickert, A. Peters, EPAC 2004  
A. Reiter et al., EPAC 2006

|   |  |
|---|--|
| Viewing screens (org. Ta)                         | Real 2D images of ion source beams                           |
| SEM profile grids<br>(at CNAO also wire scanners) | Beam profiles & positions (LEBT, Linac, MEBT)                |
| Moveable slits                                    | Beam analysis & selection of ion species (LEBT)              |
| Faraday cups                                      | Beam stop, DC / AC beam currents                             |
| DC & AC beam current transformers                 | Continuous beam current monitoring                           |
| Capacitive pick-ups / phase probes                | TOF beam energy & bunch measurements<br>(behind RFQ & Linac) |


- See contributions by [R. Cee \(next talk\)](#) and [A. Reiter \(Wednesday, 4:35 pm\)](#) for **further details and applications during routine operation & commissioning**
- **No emittance measurement installed at HIT for routine operation**  
(just during beam commissioning & at test bench at HIT, see talk by R. Cee)
- **CNAO: permanent emittance measurement devices installed along LEBT**  
(slits & wire scanners, [J. Bosser et al., EPAC 2008](#), [A. Parravicini et. al., HIAT09](#))



## HIT Injector Linac, Heidelberg, Germany


B. Schlitt, LINAC 2008

CNAO, Pavia, Italy





**MIT Injector Linac,  
Marburg, Germany  
built by Siemens /  
Danfysik**




Photos: Siemens





# 20 MV Interdigital H-Mode Drift Tube Linac (IH-DTL)



|                            |                |
|----------------------------|----------------|
| Beam energy in – out       | 0.4 – 7 MeV/u  |
| Integrated triplet lenses  | 3              |
| Accelerating gaps          | 56             |
| Tank length                | 3.8 m          |
| Inner tank height          | 0.34 m         |
| Inner tank width           | 0.26 m         |
| Drift tube aperture diam.  | 12 – 16 mm     |
| Tank voltage               | ~ 20 MV        |
| Averaged eff. volt. gain   | 5.3 MV/m       |
| Max. on axis electr. field | $\leq 18$ MV/m |
| Max. eff. gap voltage      | ~ 500 kV       |
| Quality factor             | 15200          |
| RF power loss (pulse)      | ~ 900 kW       |

[B. Schlitt et al., LINAC 2004 & LINAC 2006](#)



[Y. Lu, LINAC 2004](#)

In collaboration with IAP,  
Frankfurt University, Prof. Ratzinger

# 400 keV/u 4-Rod Type RFQ

Designed and assembled at IAP,  
Frankfurt University, Prof. Schempp


A. Bechtold et al., EPAC 2004





|                       |               |
|-----------------------|---------------|
| Beam energy in – out  | 8 – 400 keV/u |
| Electrode length      | 1.28 m        |
| Tank diameter         | 0.25 m        |
| Tank length           | 1.44 m        |
| Electrode voltage     | 70 kV         |
| RF power loss (pulse) | ~ 200 kW      |







# 400 keV/u Inter-tank Section (ITM)



# RFQ Beam Test Bench @ GSI (HIT & CNAO RFQs)



# RFQ Beam Test Bench @ GSI (HIT & CNAO RFQs)






# HIT Linac Commissioning Milestones

|                       |             |  |
|-----------------------|-------------|--|
| 2004 – 2005           | Building    | Building construction & installation of accelerator infrastructure |
| Nov 2005 – March 2006 | LEBT, ECRIS | Installation & testing of components                               |
| April – May 2006      | ECRIS       | Successful beam commissioning                                      |
| May – July 2006       | LEBT        |  |
| July – Oct 2006       | RFQ         | Installation & RF commissioning                                    |
|                       |             | Beam commissioning   |
| Oct – Dec 2006        | IH-DTL      | Installation IH-DTL & stripper section                             |
|                       |             | RF commissioning   |
|                       |             | First 7 MeV/u C <sup>6+</sup> beams                                |
| Feb 7, 2007           | Synchrotron | 1 <sup>st</sup> turn in synchrotron                                |
| March 23, 2007        | HEBT        | 1 <sup>st</sup> accelerated beam in treatment places               |
| Dec 16, 2007          | H1, H2      | C <sup>6+</sup> and proton beams in treatment quality              |


# CNAO LEBT Beam Commissioning Test Bench




- **Wire scanners (WS)** used for emittance measurements  
→ large angular acceptance ( $\pm 150$  mrad)
- **Slits (SLT)** at RFQ input matching point  
→ beam measurements at nominal field of the focusing solenoid
- **Investigation & minimization of solenoid steering**
- **Preparation of  $H_3^+$  probe beam**  
(factor 5 to 10 smaller rms emittances)

P. Posocco et al., HIAT09

## Behind RFQ & ITM




## Behind Stripper Section




- Similar test benches used at HIT Linac commissioning
- See talk by [A. Reiter \(Wednesday, 4:35 pm\)](#) for details of phase probe measurements




# HIT Ion Source Investigations – Viewing Screen Measurements (in LEBT)




**14.487000GHz**




**14.489500GHz**




**14.496000GHz**




**14.504500GHz**




**14.506500GHz**



**14.509000GHz**



**14.512000GHz**




**14.517500GHz**

Evolution of  $H_3^+$  and  $H_2^+$  beam shape with ECR frequency behind first solenoid


T. Winkelmann et al.,  
Rev. Sci. Instrum. 81, 02A311 (2010)

# RFQ Performance (CNAO)

## RFQ Acceptance Probing



## RFQ Beam Energy & Transmission



- **Adjustment of drift tube buncher integrated into RFQ to match beam energy and phase width at IH-DTL injection**
  - **RFQ Testbenches** at GSI (HIT & CNAO RFQs), DANFYSIK, and HIT
- **RFQ transmission at HIT and MIT only 30 – 40 %** (incl. solenoid & ITM)


## Improvements so far:

- **New input radial matcher** (IRM) for reduced external focusing at RFQ injection (reduction of aberration effects by solenoid focusing)
- **Mechanical design** of RFQ electrodes & tank, improved alignment of electrodes & tank, more robust RFQ tank
- **Optimized beam matching to RFQ** (emittance measurements at exact RFQ injection point, acceptance measurements using probe beams)
- **RFQ transmission at CNAO:** ~ 60 %  
**Kiel / Shanghai (Siemens):** 60 – 70 %




# Example for HIT Linac Beam Commissioning Results

### Beam energy for different RF plunger positions ( $^{12}\text{C}^{4+}$ ):







### Beam emittances behind foil stripper ( $^{12}\text{C}^{4+}$ ):



Beam emittances agree  
well with simulation results

# Example for Linac Commissioning (CNAO): Phase & Amplitude Scans, Chopper Rise Time




# LINAC Performance (CNAO)

| Ions                            | Beam Currents / $\mu\text{A}$ |           |            | Linac Transm. |
|---------------------------------|-------------------------------|-----------|------------|---------------|
|                                 | LEBT                          | Linac     | Stripped   |               |
| $\text{C}^{4+} / \text{C}^{6+}$ | $\sim 170$                    | $\sim 85$ | $\sim 115$ | 50 %          |
| $\text{H}_3^+ / \text{p}$       | 1030                          | 415       | 1200       | 40 %          |

- Linac transmission at Kiel (Siemens)  $\geq 50 \%$
- Linac design beam currents achieved at CNAO and Shanghai
- High beam brilliance matches very well the requirements of efficient multiturn injection into the synchrotron

## Carbon Ion Beam Currents (CNAO)



B. Schlitt et al., IPAC 2010



- Various beam instrumentation for beam commissioning & routine operation
- Individual beam test benches behind each injector section
- TB0 at RFQ injection point very helpful (CNAO)
- Various improvements of ECRIS & later RFQs
  
- HIT linac successfully in operation since ~ 14 years
- Availability  $\geq 99$  % w/o major breakdowns
- Very high stability & reliability
- > 6500 patients treated at HIT
- RFQ upgrades desired at HIT and MIT, further improvements proposed (revised beam dynamics, stem geometry, ...)



**Thank you for attention!**

