



# Beam Commissioning at FRIB

Speaker: Tomofumi Maruta

Facility for Rare Isotope Beams at Michigan State University

ARIES workshop, January 25, 2021

**MICHIGAN STATE**  
UNIVERSITY



U.S. DEPARTMENT OF  
**ENERGY**


Office of  
Science

# Outline of the Talk

- Brief description of FRIB injector linac
- Outline of phased beam commissioning of the linac
- Beam study results from Front-end to the 2<sup>nd</sup> linac segment
- Summary

# Outline of FRIB Injector Linac

- Accelerate all stable ion species more than 200 MeV/u by > 300 superconducting RF resonators
- Provide beam power of 400 kW for all ions on the production target
- Two folding beam line in the accelerator tunnel
  - Front-end (IS, LEBT, RFQ and MEBT), 3 linac segments (LS1~3), 2 folding segments (FS1, 2) and a beam delivery system (BDS) to the production target
- Flexibility of beam duty (CW, pulsed)
- Simultaneous multi-charge state beam acceleration
  - $^{238}\text{U}$ : 33+, 34+ from ECR ion source to the charge stripper and 76+ ~ 80+ after that
  - FS1 and FS2 bending sections are designed to ensure both achromatic and isochronous conditions




# Phased Beam Commissioning is on-going

## Phase-4 Commissioning Completed


- For the injector linac, two commissioning performance requirements defined
  - $^{36}\text{Ar}$  beam with energy  $> 200$  MeV/u and beam current  $> 20$  pnA
  - $^{86}\text{Kr}$  beam to produce  $^{84}\text{Se}$  by fragmentation
- Six-phased beam commissioning are planned from upstream
  - Beam test started at May 2017
  - Up to now, Phase 4 was successfully completed

Phase	Area with beam	Energy [MeV/u]	Date	
Phase 1	Front end (Ion source, LEBT, RFQ, MEBT)	0.5	07/2017	✓
Phase 2	Linac Segment (LS) 1 with $\beta = 0.041$ cryomodules	2	05/2018	✓
Phase 3	Rest of LS1 and first dipole of Folding Segment (FS) 1	20	02/2019	✓
Phase 4	Rest of FS1, LS2, part of FS2 to straight dump	200	03/2020	✓
Phase 5	Rest of FS2, LS3, Beam Delivery System (BDS) straight section	$> 200$	04/2021	
Phase 6	Target hall preseparator	$> 200$	10/2021	



# Front End Beam Instrumentation


- Set of diagnostics device are available for beam tuning and finding setpoints of optical devices
  - Beam profile and position measurement
    - » Allison emittance scanner
    - » Pepper pot
    - » Image viewers
    - » Wire profile monitors
    - » Beam position monitors (BPM)
  - Beam current measurement
    - » Faraday cups (FC)
    - » Beam current transformers (BCM)
  - Beam interceptive device
    - » 4-Jaw Charge selection slits
    - » Apertures
  - Intensity control
    - » Electrostatic chopper
    - » Intensity attenuators



# LEBT Beam Profile Measurements

- before the phase-1 beam commissioning, Front-end optics was developed for  $^{40}\text{Ar}$ 
  - Analysis scripts for Allison scanner, PM and image viewer were developed
  - FLAME (matrix), TRACK (PIC) and IMPACT (PIC) simulation code were prepared
- Snapshots of image viewers and a TRACK simulation are agreed well


Reconstructed RMS beam envelope by FLAME from 8 PMs and 1 Allison scanner measurements




## Allison scanner

X-Xp plane


Y-Yp plane



## Image viewer





## TRACK simulation





# Front End Beam Commissioning (Phase 1) in July, 2017

- $^{40}\text{Ar}$  and  $^{86}\text{Kr}$  were successfully accelerated to 0.5 MeV/u by RFQ
  - Beam energy was confirmed by a dipole magnet in MEBT
  - RFQ beam transmission is 85% as design
    - » Correlation of DC beam transmission and RFQ voltage is consistent with a simulation
- $^{86}\text{Kr}^{17+,18+}$  are transported to the entrance of RFQ without any optics change
  - $\Delta q/q = \sim 6\%$ , almost twice of  $^{238}\text{U}$
  - $\sim 100\%$  beam transmission to the RFQ entrance





# Beam Commissioning of the First 3 Cryomodules in Phase 2 (May, 2018)

- First beam acceleration by superconducting RF resonators
  - Accelerate Argon beam up to 2.0 MeV/u by twelve  $\beta = 0.041$  Quarter Wave Resonators (QWR) in three cryomodules
    - » Design energy: 1.5 MeV/u
- Temporary diagnostics station (D-station) was constructed after the cryomodules
  - Absolute beam energy measurement by a SiD
  - Beam profile measurements in both transverse and longitudinal phase space
  - Beam diagnostics test

Resonator and cryomodule parameters

Resonator		CA Cryomodule	
$\beta_{OPT}$	0.041	# of cavity	4
type	QWR	# of solenoid w/ corrector	2
f [MHz]	80.5	# of BPM	2
$V_{acc}$ [MV]	0.8		
$r_{apr}$ [mm]	36		




$\beta = 0.041$  (CA) cryomodules





# Highlights of Phase-2 Beam Commissioning

- Accelerate both  $^{40}\text{Ar}$  and  $^{86}\text{Kr}$  to 2.0 MeV/u by 11 SRF cavities
  - The absolute energy and longitudinal bunch size were measured by SiD
- Phase scan application developed by python script is worked well
  - Energy is calculated from time-of-flight of two BPMs
  - Only 0.2 euA is necessarily to measure bunch arrival timing w.r.t the reference RF
  - Scan at 20% design amplitude to determine driven phase and then increase its amplitude to get design energy
- Transverse and longitudinal emittance were measured in D-station
- Machine protection system is tested and activated to run high power beam

Beam energy by SiD after finishing each cavity's tuning








Longitudinal bunch size



# Longitudinal RMS Emittance Measured with Two MHB Settings

- Multi-Harmonic Buncher (MHB) is to provide bunched beam to RFQ
  - Three harmonics of 40.25, 80.5 and 120.75 MHz
- Measured longitudinal emittance with two MHB settings
  - Measure longitudinal bunch length by the SiD with varying the amplitude of 9<sup>th</sup> resonator
  - Minimum longitudinal emittance
  - Maximum beam transmission
- However the emittance with max. transmission is grater, it is still acceptable




[ $\pi$ keV/u nsec]	Meas.	Sim.
Min. emit.	0.14	0.12
Max. trans.	0.19	0.14

# Beam Commissioning of LS1 in Phase 3 (Feb. 2019)

- The functions were successfully verified
  - Four ion species of  $^{40}\text{Ar}$ ,  $^{86}\text{Kr}$ ,  $^{20}\text{Ne}$  and  $^{129}\text{Xe}$  accelerated to 20 MeV/u
  - Demonstrated charge stripping with the carbon foil stripper
    - » While 1<sup>st</sup> year user operation is planned to use rotating carbon stripper, an liquid lithium stripper will be installed for high power operation
- Further beam studies were also completed successfully
  - Transverse and longitudinal emittance after LS1 were measured
    - » No emittance growth observed for transverse
  - ~300 W beam transported to FS1b without any beam loss
    - » CW operation, and high peak current with low duty
  - Two charge state  $^{86}\text{Kr}$  acceleration with identical MEBT to FS1 setting
  - Fault scenario study
    - » One cavity and one cryomodule fault

Parameter of cryomodules






Cryo type	CA	CB
<b>Cavity</b>		
$\beta_{\text{OPT}}$	0.041	0.085
type	QWR	
f [MHz]	80.5	
$V_{\text{acc}}$ [MV]	0.8	1.8
$r_{\text{apr}}$ [mm]	36	36
<b>Cryomodule</b>		
# of cavity	4	8
# of solenoid w/ corrector	2	3
# of BPM	2	3



# Charge State Distributions after the Stripper Measured for Four Ion Beam Species

- 0.8 mg/cm<sup>2</sup> carbon foil was inserted on the beamline
- Scan 45° dipole current with monitoring magnitude of the Beam Position Monitor (BPM) signal after the charge selector slits adjusted for 4 mm horizontal aperture
  - Very low noise and high sensitivity of 0.1 eμA level beam current

- Charge states are isolated well to be selected by the charge selector




# Transverse Beam Parameters are Consistent with Design Parameters

- Transverse envelope were matched to downstream optics
  - Estimate beam envelope based on profile monitor (PM) measurements
  - Optimize four quadrupole fields for an envelope matching
    - » LS1 injection matching by MEBT last four quadrupoles
    - » FS1 injection matching by LS1 last four quadrupoles
- No significant emittance growth during LS1

## MEBT matching


$$\epsilon_{x,n,rms} = 0.13, \epsilon_{y,n,rms} = 0.11 [\pi \text{ mm-mrad}]$$

summary\_20190409\_114754\_retune\_output\_moment1\_3d.json



## FS1 reconstructed envelope

$$\epsilon_{x,n,rms} = 0.12, \epsilon_{y,n,rms} = 0.13 [\pi \text{ mm-mrad}]$$






# Fault Study: One Cryomodule Off

## Beam is Accelerated up to 19.5 MeV/u w/o Significant Losses

- All resonators and solenoids in CB09 were off
- Tune CB08 and CB10 solenoids to compensate missing solenoids
- $2\pi$  phase scan tuning to the cavities in CB10 and CB11
  - 14% higher voltage and  $-15^\circ$  synchronous phase to recover energy
  - Additional tuning will be done in LS2 to completely recover energy
- 100% BCM transmission was achieved to FS1, however beam fraction of  $5 \times 10^{-4}$  was detected with the HMR after CB09



# <sup>86</sup>Kr Two Charge States Acceleration

## Capability of LS1 Dual Charge States Acceleration Demonstrated

- Charge difference is twice of Uranium beam
  - Beam is more mismatched than design
- Everything is tuned for <sup>86</sup>Kr<sup>17+</sup>
  - Beam trajectory aligned within  $\pm 1$  mm
  - Transverse matching was conducted at the FS1 entrance

$${}^{86}\text{Kr}^{17+,18+} \quad \frac{\Delta q}{q} = 5.7\% \quad \longleftrightarrow \quad \frac{\Delta q}{q} = 3.0\% \quad {}^{238}\text{U}^{33+,34+}$$


- ECR IS and LEBT are tuned to <sup>86</sup>Kr<sup>18+</sup> because a velocity equalizer at the RFQ entrance is absent at present
  - Extraction voltage is set for 18+ to be 12 keV/u
  - Scale LEBT optical elements by 17/18

Energy after LS1

[MeV/u]	17+	18+
LS1 end	20.30	20.26

- While transmission is 100%, trajectory is displaced up to 7 mm



**Beam trajectory of 17+ and 18+ along LS1 – FS1**



# Misalignment of Front-end Elements Cause the Trajectory Displacement

- One of the main reason of trajectory displacement is misalignment of front-end optical elements
- All elements were aligned within requirement of 0.2 mm when installed in 2017
- However, the floor was deformed by cryomodule weight installed later
  - Optical elements were misaligned up to +/-0.5 mm
- Simulation shows the

Vertical misalignment of RFQ and MEBT



$\Delta(17-18)$	dx [mm]	dxp [mrad]	dy [mm]	dyp [mrad]
MEBT end	-0.7	2.2	-4.7	3.1

# Beam Commissioning of LS2 (March and October, 2020)

- The functions were successfully verified
  - $^{36}\text{Ar}$  was accelerated to 204 MeV/u in LS2, and  $^{129}\text{Xe}$  and  $^{86}\text{Kr}$  were > 180 MeV/u
    - »  $^{129}\text{Xe}$  setting was scaled to  $^{86}\text{Kr}$  and LS1 downstream to LS2 resonator were tuned to compensate energy loss difference at the charge stripper
- Multi-charge state accelerations are demonstrated
  - Achromatic and isochronous condition in FS1 bending section
  - Three charge states of  $^{129}\text{Xe}$
  - Two charge state of  $^{86}\text{Kr}$
  - No beam loss was observed except for near the stripper and beam dump




Cryo type	CC	CD
<b>Cavity</b>		
$\beta_{\text{OPT}}$	0.29	0.53
type	HWR	
f [MHz]	322	
$V_{\text{acc}}$ [MV]	2.1	3.7
$r_{\text{apr}}$ [mm]	40	40
<b>Cryomodule</b>		
# of cavity	6	8
# of solenoid w/ corrector	1	1
# of BPM	0	0





LS2: 12 x  $\beta = 0.29$  (CC) and 12 x  $\beta = 0.53$  cryomodules

# Three Charge State $^{129}\text{Xe}$ Acceleration in LS2

- Three charge states of  $^{129}\text{Xe}^{49+,50+,51+}$  are simultaneously accelerated by LS2
- Measured transverse and longitudinal beam positions are close to design
- Beam ellipses after LS2 are overlapped so effective emittance is not large and sufficient margin to downstream acceptance



5 times RMS ellipse vs. acceptance after LS2






# Test of Ion Species Change

- In the user operation, it can be required to change the ion species in short time, so need to minimize tuning procedure
- Test the procedure to switch  $^{129}\text{Xe}$  to  $^{86}\text{Kr}$ 
  - Scale all optical elements and resonators by charge-to-mass ratio
  - Reduce the field of last two resonators in LS1 to get identical energy after the stripper
  - Rephase bunchers in FS1
  - Rephase first resonator in LS2 and shift other LS2 resonators in same amount
- Energy after LS2 is almost identical to  $^{129}\text{Xe}$

Energy after LS2


[MeV/u]	$^{129}\text{Xe}$	$^{86}\text{Kr}$
	181.09	181.13




# Developments of High Level Applications (HLA)

- High level applications have been developed for beam study
  - All applications are registered to the HLA launcher
    - So far 37 applications are registered
    - Operator are available for limited applications
- Python +Qt platform
  - Available on any operation system

## HLA Launcher



## Phase scan application



## Matching application



# Summary

- Up to now, phase-4 beam commissioning of the FRIB injection linac was successfully completed to meet Key Performance Parameter
  - Beam energy was already reached to the requirement for key performance parameter
    - »  $^{36}\text{Ar}$ : 204 MeV/u,  $^{86}\text{Kr}$  and  $^{129}\text{Xe}$  > 180 MeV/u
- Further studies have been conducted
  - Transverse and longitudinal emittance were measured in several locations
  - Proved the multi-charge state simultaneous acceleration and transportation in LEBT, LS1 to LS2
- For user operation, we conducted several beam studies to improve beam availability and beam power
  - Recovery study of one resonator or cryomodule fault
  - Charge state distribution and energy loss at the carbon charge stripper
    - » Li stripper will be installed for high power operation
  - Switching ion source species

# Acknowledgments

- I like to thank my colleagues for significant contribution to this work
- Work supported by the U.S. Department of Energy Office of Science under Cooperative Agreement DE-SC0000661, the State of Michigan and Michigan State University.

