

DECREASING THE FOOTPRINT FOR A NEW SR FACILITY - BESSYIII

Decreasing the footprint for a new SR facility

Jens Völker - HZB

7th ESSRI workshop 2024 Madrid




BESSYIII

Green field option (BESSYIII / BESSYII):

- 40% larger circumference
- 48% higher beam energy
- 66% higher beam current
- >100% larger building complex


Goal for power consumption:
**over all power for BESSYIII
equal or less than BESSYII !**



BESSY III (2035)

- > MBA (6BA) lattice (16 arcs)
- > ~340m circumference
- > hor. emittance <100pmrad
- > energy 2.5GeV
- > up to 500mA beam current

OVERVIEW



construction
installation
fabrication




<https://www.hausjournal.net>



Cryoelectra



<https://www.wme.de>




LCA analyse

OUTLINE:


- Accelerator Components
 - > RF hardware
 - > magnets
- Building
 - > energy production
 - > using waste heat
 - > construction

Using BESSYII+ as test bed for these developments

ACCELERATOR COMPONENTS



Ongoing projects to reduce running coasts for RF and magnet systems:




Quadrupoles



Homogenous bends

Reverse bends

Sextupoles



	Dipole	Quadrupole	Reverse Bends	Sextupole
Field/gradient	0.6-0.8 T	50-90 T/m	80 T/m + 0.18-0.25 T	<4000 T/m ²
Quality	$0.1 \cdot 10^{-4}$	$\sim 1 \cdot 10^{-4}$	$\sim 1 \cdot 10^{-4}$	tbd
Stability	$< 1 \cdot 10^{-4}$			
Variation	-	<10%	5%	100%
Power consumption (PM / electro)	0 kW / 290 kW	<25 kW / ~600 kW		>100 kW



	BESSY III conventional	BESSYIII PM
96 Dipoles	ca. 290 kW	0 kW
446 Quadrupoles	ca. 600 kW	< 25 kW
NL Multipoles (240 Sextupoles, 32 Octupoles)	ca. 130kW	
Total	ca. 1000 kW	ca. 150 kW

Ongoing projects to reduce running costs for RF and magnet systems:

RF-components



500MHz SSA

Cryoelectra



500MHz Cavities at BESSYII

RF 2.0 Project (EU Horizon 2023/2024) WP2.2



RF Technology for Particle Accelerators and Fusion *Cryoelectra*

Effect of drain voltage on efficiency

Pout [W]	40V Efficiency (%)	44V Efficiency (%)	48V Efficiency (%)	50V Efficiency (%)
0	10	10	10	10
2000	35	30	28	25
4000	55	48	45	40
6000	65	58	52	48
8000	68	62	58	52
10000	69	65	62	55
12000	70	68	65	58
14000	70	70	68	60
16000	70	70	70	60


- By adjusting the bias point, the efficiency can be optimized for lower output powers
- Setting the right bias point dynamically requires intricate knowledge of the whole amplifier system
- This process shall be automated by the proposed control algorithm to make the efficiency improvements usable by the accelerator's operator

Courtesy B. Nordmann
(Cryoelectra)




This project has received funding from the European Union's Europe research and innovation program under grant agreement **No 101131850**

Ongoing projects to reduce running coasts for RF and magnet systems:



- > PM driven QP magnet with CoFe Pole Shoes (gradient up to 120T/m)
- > Pole Shoe Tip and chamfer are numerical optimized to maximize b_2 (quadrupole) and to minimize central and/or integrated b_6 , b_{10} and b_{14}




- > up 24 tuning plates (10mm thick CoFe) will be installed in parallel to PM blocks
- > position of plates reduces the max. magnetic flux (short circuit)



- > the plates are mechanical connected
- > position inside yoke can be changed via motors (slow)
- > field strength can be reduced by approx. 40% ($\sim 0.5\%/mm$) (or $\pm 20\%$ to operating point)

Ongoing projects to reduce running costs for RF and magnet systems:

Homogeneous PM-Dipole for BESSYIII




- Increased pole shoe width for straight magnet
- central notch to further flatten the field
 - > homogenous field for the full bended beam

8 **PM blocks** (40mm x 25mm) in transverse plane
 -> 14 **thermal shim plates** (< 4mm thickness)


-> idea for two prototypes: **one with new PM blocks and one with recycled PMs**

PM Triplet for BESSYII+ to replace a 20kW dipole in 2025



- > 300mm hom. PM dipole magnets with (0.8T – 1.1T - 0.8T)
- > NdFeB PM with $B_r=1.3T$
- > incl. steerer coils to adjust int. field by 4%

PM bending magnet for BESSYII+ main bending magnets



- > hom. PM bending magnet
- > up to 1.4T (4e-5 error $\pm 20mm$)
- > NdFeB PMs with $B_r=1.42T$
- > gap 30mm
- > idea replace two existing electromagnets in BESSYII
- > temperature stabilized: NiFe

CONSTRUCTION WORK -> RUNNING COSTS (PV + WASTE HEAT)



Ongoing projects to reduce running costs: Energy production

PV-facade study @ TestingHall 2

- > 360 commercial solar modules
- > installed on three sides of the building
- > 28 MWh per year
- > 120 measurements points and sensors




1.2MW
Waste heat



Evaporating cooling system


New Buildings on Campus (2027)

Technikum
(Laboritories and office)



CatLab
(Laboratories)



	Technikum	CatLab
# PV	292	106
Peak power	128.5 kW	64 kW
kWh/a	~84000	~42000

Ongoing projects to reduce running costs: Energy production

PV-facade study @ TestingHall 2

- > 360 commercial solar modules
- > installed on three sides of the building
- > 28 MWh per year
- > 120 measurements points and sensors




1.2MW
Waste heat



Evaporating cooling system

New Buildings on Campus (2027)


Technikum
(Laboritories and office)




CatLab
(Laboratories)



Option for BESSYIII
Energy-harvesting potential by PV-skin: **3 GWh/a**



Ongoing projects to reduce running costs: Energy production



1.2MW
Waste heat



New Buildings on Campus (2027)

Technikum
(Laboritories and office)




CatLab
(Laboratories)



2.42 MW heating

Ongoing projects to reduce running costs: Energy production



New Buildings on Campus (2027)

Technikum
(Laboritories and office)



CatLab
(Laboratories)




1.44 MW

2.42 MW heating

Option for BESSYIII

- ➔ Implementation of heat recovery direct from the beginning of BESSYIII into the local network
- ➔ Realization and scope of such a project has to be discussed with local network provider
- ➔ Just starting

CONSTRUCTION WORK -> INITIAL COSTS



POSSIBLE ADJUSTMENTS IN THE CONSTRUCTION PHASE

- material-optimized construction**
 e.g. use of carbon concrete to save concrete, which must have minimum coverings to protect the conventional reinforcing steel from corrosion
- optimized construction shape**
 optimize shape and cross section of the ground plate for **high stiffness and vibration dampening**, but **less concrete**



Example: Cube in Dresden - the world's first building made of carbon concrete (from: www.bba-online.de/news/cube-neues-bauen-mit-carbonbeton/#slider-)



Comparison reinforcing carbon and steel (from <https://www.carbocon.de>)




Standard monolithic block

-> **ca. 30000m³ concrete**
(5% reinforcement)

CO₂ equiv. concrete (t) ca. 10000

CO₂ equiv. steel (t) ca. 17500

Options to reduce concrete:



Recycled concret -> 10-18% less CO2



POSSIBLE ADJUSTMENTS IN THE CONSTRUCTION PHASE

- material-optimized construction**

e.g. use of carbon concrete to save concrete, which must have minimum coverings to protect the conventional reinforcing steel from corrosion

- optimized construction shape**

optimize shape and cross section of the ground plate for **high stiffness and vibration dampening**, but **less concrete**



Standard monolithic block

-> ca. 30000m³ concrete (5% reinforcement)	
CO ₂ equiv. concrete (t)	ca. 10000
CO ₂ equiv. steel (t)	ca. 17500

Options to reduce concrete:

-> Optimization via FEM calculation (static and dynamic parameters) based on measured vibration spectra and assumed load distributions



Example: Cube in Dresden - the world's first building made of carbon concrete (from: www.bba-online.de/news/cube-neues-bauen-mit-carbonbeton/#slider-intro-1)




Comparison reinforcing carbon and steel (from <https://www.carbocon.de>)

-> different cross sections and material distributions:




-> different shapes of the ground plate:



NEW MAGNET LABORATORY FOR PM AND UNDULATOR DEVELOPMENTS

renting laboratory space instead of rebuild it

- > necessary for a new MagnetLab for PM construction and tests
- > found a 1300 m² space for storage/office/construction/tests next to our campus
- > can be used for all ongoing magnet projects in the next 10-15 years
- > idea: modular installations can be deassembled after project time
(we can ends the contract after finishing the big projects)
- > in best case: all magnets for BESSYIII can be assembled and tested there
 - > we do not need this space as part of our technical hall for BESSYIII (>4000m²)
 - > costs and carbon footprint can be reduced!




- 210 m² construction area (girder and magnets)
- 140 m² test in thermal stabilized chambers
- 140 m² warm tests
- 140 m² storage for magnets and magnet components
- 140 m² workshop and storage
- 100 m² office/IT/etc.

SUMMARY

- > construction work has most impact for initial GWP
- > optimize material consumption
- > rent instead of own construction

- > decrease running costs
- > install direct energy production
- > Using heat recovery

- > clarify material sources to minimize GWP
- > Recycling?



<https://www.architects.org/news/the-new-net-zero>

